

## Humboldt State University Automatic Sliding Door Replacement

### 1. Project Description:

Replacement of selected automatic sliding doors and glazing at various locations on the campus of Humboldt State University (HSU) in Arcata California.

Prevailing wage is required.

### 2. Bid Details:

#### A. Pre-Proposal Onsite Discovery

- a. The pre-bid meeting will be optional, December 17, 2021. Meet at Library Main Entrance, 1961 Sequoia Mall. Arcata, CA. 95521 at 1pm.
- b. Arrangements can be made if contractors are unable to make the pre-bid meeting and would still like to see the project locations.

#### B. Project Documents

- a. Dimensions on project documents are estimates and the contractor will need to field measure. HSU does not take responsibility for dimensions.

#### C. Basis of Design

- a. Bid documents include Stanley as basis of design. Bids containing equivalent equals will be accepted.

#### D. Submittals:

- a. Door and Hardware submittals should be delivered to HSU within 15 days of being awarded the project.

### 3. Scope of Work:

#### A. Demolition:

- a. Remove existing sliding doors identified on project floor plans and recycle material. Contractor to reuse existing openings if possible.
- b. Library storefront system demo to include the vents above doors at both locations
- c. All exterior openings need to be secured at the end of each work day and no more than one opening, per building, should be removed at the same time.
- d. Job site should remain safe at all times. Pedestrian detours to be set up and agreed upon with contractor and HSU.

B. Construction:

- a. New doors and needed framing to match existing in color and style.
- b. Installer to supply and install all new door hardware that is included on the specifications as basis for design. HSU to supply the wiring to the doors for the electronic locks as well as the wall mounted card reader locations.
- c. Library doors to get new glazing in areas above sliding doors where vents were removed.
- e. All work to be inspected by HSU

3. Project Schedule:

- February 11, 2022 Submittals due
- February 12, 2022 work can begin at the Library, Jolly Giant and University Center
- Project Completion by March 18<sup>th</sup>, 2022